CAPABILITY STATEMENT · NEW CONSTRUCTION

CAROLUX INSULATION

(704) 228-2729
team@caroluxinsulation.com
caroluxinsulation.com/builders

SCOPE

Insulation subcontracting for new construction, renovation and tenant work. Attic and ceiling, exterior and interior walls, floors over crawl space, rim and band joists, crawl space ground vapor barrier, and air sealing.

MATERIALS

Fiberglass	Batt and blown-in	Owens Corning AttiCat, Pink Next Gen
Mineral wool	Batt	Rockwool. Premium tier and interior sound walls
Rigid foam board	Cut and sealed	Rim and band joists
Vapor barrier	8 to 10 mil	Americover. Crawl space ground cover

ASSEMBLIES AND R-VALUE

Attic and ceiling	Blown fiberglass, or batt where access is tight	R-30 to R-60
2x4 exterior wall	Fiberglass or mineral wool batt	R-13 to R-15
2x6 exterior wall	Fiberglass or mineral wool batt	R-19 to R-21
Floor over crawl space	Fiberglass batt between the joists	R-19 to R-30
Rim and band joist	Rigid board, cut and sealed	By thickness
Interior wall	Mineral wool batt	For sound
Crawl space ground	Americover vapor barrier	Vapor, not R
Air sealing	Before insulation, every assembly we insulate	Included

Ranges are what we commonly install, not a code table. Your drawings and compliance path set the target, and we install to the value specified on them.

RESPONSE AND SCHEDULE

Written scope and price by the next business day after receiving plans. Every bid is a scope letter: inclusions, exclusions, clarifications, and any alternates priced separately. If we cannot hold the window you need, you get that in the same reply rather than a slipped date later.

DOCUMENTATION

Every bay photographed with a depth reference before it is covered. The photo set is delivered to the builder, so what is behind the drywall stays on record.

QUALITY STANDARD

Installed to the RESNET Grade I standard as defined in ANSI/RESNET/ICC 301. A HERS rater assigns the grade; we install to the standard and document it. No installer can promise a HERS score, a blower-door result, or a code-compliance outcome.

PERSONNEL

An owner, or a directly supervised team member, is on every job, and an owner signs off before the work is covered. Tony Kermis is a former North Carolina home inspector.

INSURANCE AND PAPERWORK

General liability insurance; certificate of insurance on request or with the bid. W-9 on request. Carolux Insulation LLC, a North Carolina limited liability company. All work carries a 2-year workmanship guarantee.

NOT OFFERED

Spray foam, closed-cell or open-cell.

SERVICE AREA

Day to day: Charlotte, Huntersville, Pineville, Matthews, Mint Hill, Concord, Harrisburg, Belmont, Cramerton, Gastonia, Lowell, Mount Holly, Stanley. For new construction, commercial and tenant bids there is no radius. Mobilisation is a line item, not a reason to say no. Send the set and we will price it.